

4-041488

7-1 15-051-02073-000

E-88,290

API number: 15- - 1958

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW /4 SEC. 27, 11 S, 16 W
1980 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease Madsen well # 1-27

Operator: Berexco, Inc.

County Ellis

Address: Box 723

Hays, Kansas 67601

Well total depth 3316 feet

Conductor Pipe: 0 inch @ 0 feet

Surface pipe 8 5/8 Inch @ 917 feet

CWC - 425 sx

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Allied Cementing

License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 1 Month: July Year: 93

Plugging proposal received from: George Jorgensen

Company: Beren Corporation

Phone: _____

Were: 5 1/2" casing set @ 3315' w/100 sx. cement. Perf. @ 2993'-3144'.

W.L.M. 3100' - T.O.F. @ 1500' - Anhy. @ 917'.

Ordered 325 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:15A.M, Day: 1, Month: July, Year: 93

Actual plugging report: Hooked-up to 8 5/8" S.P. Squeezed in 105 sx. cement with 100# hulls in cement. Max. 500#. S.I.P. 400#.

Hooked-up to 5 1/2" casing. Squeezed 25 sx. cement followed with 200 sx. cement with 400# hulls in cement. Max. 500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD X BAD ____ Anhy. plug: YES X NO ____

Bottom plug(in place): YES X, CALC ____, NO ____ Dakota plug: YES X, NO ____

Plugged through TUBING ____, CASING X. Elevation: _____

I did [X] / did not [] observe the plugging.

INVOICED

DATE 8-24-93

BY, NO 38391

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1993
(agent) CONSERVATION DIVISION
Form CP-2/3 Wichita, Kansas