

3-28

4-070090

RECEIVED
KANSAS CORP COMM

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-20,401-~~0001~~

NW SE SE /4 SEC. 27, 11 S, 16 W
990 feet from S section line
990 feet from E section line

Operator license# 6790

Lease: Bowlby "B" Well # 1-OWWO

Operator: CB/JB Oil

County: Ellis 109.36

Address: P.O. Box 531
Russell, Kansas 67665

Well total depth 3365 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 925 feet
W/450 sxs.

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: CB/JB Oil License# 6790

Address: P.O. Box 531 - Russell, Kansas 67665

Company to plug at: Hour: 11:30 A.M. Day: 28 Month: March Year: 1998

Plugging proposal received from: Bill Clair

Company: CB/JB Oil Phone: 785-885-4652

Were: 8 5/8" set at 925' w/450 sxs cement. 4 1/2" casing set at 3361' w/150 sxs.
Perfs at 2726' - 2730'; 2958' - 2961'; 3013' - 3016'; 3071' - 3075'; 3081' - 3083';
3123' - 3124'; 3142' - 3146'; 3162' - 3165'; 3194' - 3198'; 3282' - 3302'; 3328' - 3333'.
Perforated 915' and 450'. Ordered 210 sxs of Mid Con II. Plug down casing.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 4:45 P.M., Day: 28, Month: March, Year: 1998

Actual plugging report: Halliburton (Excel) perforated 915' and 450'. Halliburton pumped 210 sxs of Mid-Con II with 700# hulls. No pressure. Slight blow on annulus. Waited on more cement 2 hours. Pumped total of 225 sxs down 4 1/2" casing. Max. P.S.I. 500#. S.I.P. 500#. Did not circulate. Pumped 45 sxs of Mid-Con II with 100# hulls. Max. P.S.I. 500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD BAD _____
Bottom plug(in place): YES , CALC _____, NO _____
Plugged through TUBING _____, CASING .
Anhy.plug: YES NO _____
Dakota plug: YES , NO _____
Elevation: 1760 GL

I did / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE

4-8-98

INV. NO.

50336

3-28 JUN 17 1998