

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich North ProjectAddress AB oil well Gas Well Other well as hereinafter indicated: Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: Day: 28 Month: 7 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All Part XXXXXX None Operations Completed: Hour: Day: 28 Month: 7 2009Actual Plugging Report: 200' of 1" pipe was removed. The well was then perforated at 600', 300',and 150'. A 1" cement string was lowered to 800' inside the 2" production pipe. The well was pumped full ofcement from btm to top thru this cement string. A total of 23 sacks of portland cement were used to plugwell. The well was cut off below plow depth and the location restored.

RECEIVED

AUG 20 2009

Remarks: Control # 20090028-011. Could find no record of this well in District III files, or RBDMS
(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN