

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19810-00-00
SW SW SE Sec/Twp/Rge Sec 9 T29S R17E
293 (GPS) feet from south section line
1980 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Stich North Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Stich North-Martin gps# MAR 03
County Wilson
Well Total Depth 850 (est) feet
Production Pipe: 2 Size Feet NA
Surface Casing: NA Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 1 Month: 7 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All XXXXXX Part _____ None _____

Operations Completed: Hour: _____ Day: 1 Month: 7 2009

Actual Plugging Report: A 1" pipe was lowered to 600' to check for obstructions and for open hole.

The 1" pipe was removed and the well perforated at 600', 450', and 300'. A 1" cement string was then washed to 825' and the well pumped full of cement from btm to top thru this cement string. A total of 65 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: Control # 20090028-013

(If additional description is necessary, use BACK of this form.)

SEP 21 2009

CONSERVATION DIVISION
WICHITA, KS

I did observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN