

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich North Project

Address _____

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 2 Month: 10 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, IncPhone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 2 Month: 10 2009Actual Plugging Report: 3' of 12" surface pipe was set to bring well to surface. A 1" cement stringwas lowered down the inside of the 2" pipe to 600' to check for obstructions. The cement string wasremoved and the the well perforated at 600', 300' and 150'. A 1" cement string was lowered down theinside of the 6.25" pipe to 700'. A 0.5" cement string was lowered down the outside of the 6.25" pipe to125'. The well was pumped full of cement thru these cement strings. A total of 27 sacks of portlandcement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

Remarks: Control # 20090028-002(If additional description is necessary, use BACK of this form.)

NOV 09 2009

KCC WICHITA

I did not observe this plugging.

Signed: _____

TECHNICIAN