

To:
 STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-205- 19814-00-00
 NE SE SE Sec/Twp/Rge Sec 9 T29S R17E
1042 (GPS) feet from south section line
627 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
 Operator: State Of Kansas Fee Fund
 Name & Stich North Project
 Address _____
 AB oil well XXXXXX Gas Well _____

Lease/Well# Stich North - Wiles gps# STI 04
 County Wilson
 Well Total Depth 850 (est) feet
 Production Pipe: 2 Size Feet NA
 Surface Casing: NA Size Feet NA
 SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 15 Month: 10 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 15 Month: 10 2009

Actual Plugging Report: 5' of 12" surface pipe was set to bring well to surface. The well was drilled to 400' inside the 2" pipe. (The contractor indicated the wellbore appeared to be open hole at approx 180' in depth.) The outside of the 2" pipe was washed to 125' where the pipe hit hard. A 1" cement string was lowered down the inside of the 2" pipe to 400'. A 1" cement string was lowered down the outside of the 2" pipe to 80'. The well was pumped full of cement from btm to top thru these cement strings. A total of 80 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
 KANSAS CORPORATION COMMISSION

Remarks: Control # 20090028-004

(If additional description is necessary, use BACK of this form.)

NOV 19 2009

I did not observe this plugging.

CONSERVATION DIVISION
 WICHITA, KS

Signed:

Alan M. Dunning
 TECHNICIAN