

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Stich North Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

API NUMBER 15-205- 19815-00-00  
NE SE SE Sec/Twp/Rge Sec 9 T29S R17E  
780 (GPS) feet from south section line  
220 (GPS) feet from east section line

Lease/Well# Stich North - Wiles gps# STI 05  
County Wilson  
Well Total Depth 850 (est) feet  
Production Pipe: 2 Size Feet NA  
Surface Casing: NA Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 28 Month: 7 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 28 Month: 7 2009

Actual Plugging Report: 5' of 12" surface pipe was set to bring well to surface. A 1" pipe was lowered to 600' The 1" pipe was removed and the well was perforated at 600', 300, and 150'. A 1" cement string was lowered to 700' inside the 2" pipe. The well was pumped full of cement from btm to top thru this cement string. A total of 25 sacks of portland cement were to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
AUG 20 2009

Remarks: Control # 20090028-005  
(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did observe this plugging.

Signed: Alan M. Dunning  
TECHNICIAN