

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich North Project

Address \_\_\_\_\_

AB oil well XXXXXX Gas Well \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 10 Month: 7 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by:

Alan M. Dunning


TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXOperations Completed: Hour: \_\_\_\_\_ Day: 10 Month: 7 2009

Actual Plugging Report: 8' of 12" surface pipe was set to bring well to surface. A 1" cement string was washed down the inside of the 2" production pipe to 700'. A 1" cement string was washed down the outside of the 2" production pipe to 575'. The well was pumped full of cement from btm to top thru these cement strings. A total of 240 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090028-008(If additional description is necessary, use BACK of this form.)I did not observe this plugging.

Signed:

  
 \_\_\_\_\_  
 TECHNICIAN

RECEIVED

AUG 20 2009

KCC WICHITA