

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich North Project

Address \_\_\_\_\_

AB oil well XXXXXX Gas Well \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 1 Month: 10 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, IncPhone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part XXXXXX None \_\_\_\_\_Operations Completed: Hour: \_\_\_\_\_ Day: 1 Month: 10 2009Actual Plugging Report: A 1" cement string was lowered down the 2" production pipe to 600' tocheck for obstructions. The cement string was removed and the well perforated at 600', 300', and 150'. A 1"cement string was then lowered down the 2" production pipe to 650'. The well was then pumped full ofcement from btm to top thru this cement string. A total of 169 sacks of portland cement were used to plugwell. The well was cut off below plow depth and the location restored.

RECEIVED

Remarks: Control # 20090028-010

(If additional description is necessary, use BACK of this form.)

NOV 09 2009

I partially observed this plugging

Signed:

Alan M. Dunning  
TECHNICIAN

KCC WICHITA