

To:  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Stich North Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 1 Month: 10 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part XXXXXX None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 1 Month: 10 2009

Actual Plugging Report: 7' of 12" surface pipe was set to bring well to surface. A 1" pipe was lowered to 600' to check for obstructions. The 1" pipe was removed and the well perforated at 600', 300', and 150'. A 1" cement string was then lowered to 700' and the well pumped full of cement. A total of 35 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

NOV 09 2009

Remarks: Control # 20090028-039. This well is a close match to Wiles #N-3 (15-205-90557-00-00)  
(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I partially observed this plugging

Signed:

Alan M. Dunning  
TECHNICIAN