

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich North Project

Address _____

AB oil well XXXXXX Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 28 Month: 7 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 28 Month: 7 2009Actual Plugging Report: 6' of 10" surface pipe was set to bring well to surface. A 1" pipe waslowered to 600' The 1" pipe was removed and the well was perforated at 600', 300', and 150'. A 1" cementstring was lowered to 725' inside the 2" pipe. The well was pumped full of cement from btm to top thru thiscement string. A total of 21 sacks of portland cement were to plug well. The well was cut off below plowdepth and the location restored.

RECEIVED


AUG 20 2009

Remarks: Control # 20090028-040(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did not observe this plugging.

Signed:



TECHNICIAN