

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19833-00-00
NE NW NE Sec/Twp/Rge Sec 16 T29S R17E
5074 (GPS) feet from south section line
1288 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Stich North Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Stich North-Wiles gps# MCD 10
County Wilson
Well Total Depth 850 (est) feet
Production Pipe: 2 Size Feet NA
Surface Casing: 6 Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 29 Month: 6 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.Plugging Proposal Received by: Alan M. DunningPlugging attended by Agent: All _____ Part XXXXXX ^{TECHNICIAN} None _____Operations Completed: Hour: _____ Day: 29 Month: 6 2009

Actual Plugging Report: 425' of 1" pipe was removed from well. A 1" cement string was washed down the inside of the 2" production pipe to 425'. A 1" cement string was washed down the outside of the 2" production pipe to 300'. The well was pumped full of cement from btm to top thru these cement strings. A total of 40 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 21 2009

Remarks: Control # 20090028-025

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN