

To:  
 STATE CORPORATION COMMISSION  
 Wichita State Office Bldg. - PLUGGING SECTION  
 130 S. Market, Room 2078  
 Wichita, Kansas 67202

API NUMBER 15-205- 19836-00-00  
 SW NW NE Sec/Twp/Rge Sec 16 T29S R17E  
4505 (GPS) feet from south section line  
2254 (GPS) feet from east section line

# TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
 Operator: State Of Kansas Fee Fund  
 Name & Stich North Project  
 Address \_\_\_\_\_  
 AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Stich North-Wiles gps# MCD 13  
 County Wilson  
 Well Total Depth 850 (est) feet  
 Production Pipe: 2 Size Feet NA  
 Surface Casing: NA Size Feet NA  
 SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 22 Month: 6 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 22 Month: 6 2009

Actual Plugging Report: A 1" pipe was lowered inside the 2" production pipe to 600' to check for obstruction and for open hole. The 1" pipe was removed and the well perforated at 600', 450', and 300'.

A 1" cement string was then washed to 750' and the well pumped full of cement from btm to top thru this cement string. A total of 26 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090028-028

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning  
 TECHNICIAN

RECEIVED

AUG 27 2009

KCC WICHITA