

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19838- 00-00
SW NW NE Sec/Twp/Rge Sec 16 T29S R17E
4384 (GPS) feet from south section line
2028 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Stich North Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Stich North-Wiles gps# MCD 15
County Wilson
Well Total Depth 850 (est) feet
Production Pipe: 2 Size Feet NA
Surface Casing: NA Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 22 Month: 6 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 22 Month: 6 2009Actual Plugging Report: A 1" pipe was washed inside the 2" production pipe to 600' to check forobstruction and for open hole. The 1" pipe was removed and the well perforated at 600', 450', and 300'.A 1" cement string was then washed to 775' and the well pumped full of cement from btm to top thru thiscement string. A total of 27 sacks of portland cement were used to plug well. The well was cut off belowplow depth and the location restored.

RECEIVED

AUG 27 2009

Remarks: Control # 20090028-030(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN