

To:  
 STATE CORPORATION COMMISSION  
 Wichita State Office Bldg. - PLUGGING SECTION  
 130 S. Market, Room 2078  
 Wichita, Kansas 67202

API NUMBER 15-205- 19839-00-00  
 NE NW NE Sec/Twp/Rge Sec 16 T29S R17E  
4828 (GPS) feet from south section line  
1561 (GPS) feet from east section line

# TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
 Operator: State Of Kansas Fee Fund  
 Name & Stich North Project  
 Address \_\_\_\_\_  
 AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Stich North-Wiles gps# MCD 16  
 County Wilson  
 Well Total Depth 850 (est) feet  
 Production Pipe: 2 Size Feet NA  
 Surface Casing: NA Size Feet NA  
 SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 29 Month: 6 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part XXXXXX None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 29 Month: 6 2009

Actual Plugging Report: 4' of 12" SC was set to bring well to surface. A 1" pipe was lowered inside the 2" pipe to 400' to check for obstruction and for open hole. The 1" pipe was removed and the well perforated at 600', 450', and 300'. A 1" cement string was then run to 725' and the well pumped full of cement from btm to top. A total of 28 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
 KANSAS CORPORATION COMMISSION

Remarks: Control # 20090028-031

SEP 21 2009

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
 WICHITA, KS

I partially observed this plugging

Signed:

Alan M. Dunning  
 TECHNICIAN