

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission,  
800 Bittling Building,  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NOV 13 1936  
11-13-1936  
Russell

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330 from S. line center 1/2 of SE 1/4 County. Sec. 30 Twp. 13 Rge. 12 (E) (W)

Lease Owner. Equity Gas Co  
Lease Name. Cora Shaffer Well No. 1  
Office Address. Independence, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole  
Date, well completed last 2' drilled to 3358 - 5-14 1936  
Application for plugging filed 9-11 (Dental with C.T. Alexander) 1936  
Application for plugging approved 9-12 1936  
Plugging Commenced 9-12 1936  
Plugging Completed 9-17 1936  
Reason for abandonment of well or producing formation Not Commercial

If a producing well is abandoned, date of last production ✓ 1936

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.T. Alexander

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3358 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Water Sand	1/2 BxH	275	280	15"	369-6	369-6
	HFX	400	410	12"	478-4	478-4
gas sand Speka	Small Show	2345	2347	10"	775-3	775-3
Roswald 1st Break	Small Show	2989	2991	8"	2423	2423
last Break	✓	3218	3225	6"	3002	2972
Siliceous	water	3347	3356	5"	3353	3200-10"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

*This well was plugged back from 3358 to 3225 to oil show 3218-3225 & air drilled but no good. Hole filled with mud 3358 to 3285 Rock, steel cutting head used & cement to 3225, & 5" casing raised & cemented at 3026. Hole filled with mud introduced into hole by buckets from 3225 to 2500. All of casing was pulled, hole bridged at 3934 a 15 foot cement plug to 0378, & mud being pulled in by slip from slush found from 378 to top of hole, put bottom of cellar. Hole at top of cellar bottom was cemented with 5' of cement & sand capping top 10-20-36*

PLUGGING  
FILE NO. 20T13R12W  
BOOK PAGE 61 LINE 35

(If additional description is necessary use BACK of this sheet)


Correspondence regarding this well should be addressed to \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF ROSSELL, SS. HERBERT PHOTON (employee of ~~owner~~ ~~operator~~) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert Photon  
Bunker Hill Haus  
(Address)

day of NOV 12 1936



James J. Shoman  
Notary Public.

