

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-23227-0000

LEASE NAME Lawson

WELL NUMBER 1

990 Ft. from ^N Section Line

330 Ft. from ^W Section Line

SEC. 36 TWP. 13 RGE. 12 (E or W)

COUNTY Russell

Date Well Completed 1-30-03

Plugging Commenced 1-30-03

Plugging Completed 1-30-03

LEASE OPERATOR Grady Bolding Corporation

ADDRESS PO Box 486, Ellinwood, KS 67526

PHONE (620) 564-2240 OPERATORS LICENSE NO. 7383

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-30-03 (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3,042'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	458'	Cmtd. w/250 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Push plug to 715', pump 50 sax cement on plug; push plug to 350', pump 50 sax cement on plug; push wiper plug to 40', dump 10 sax on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address 326 Main, Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

Contractor
(Employee of ~~XXXXXX~~) or ~~XXXXXX~~


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 11th day of February, 192003

My Commission Expires: _____



Notary Public

FEB 12 2003


KCC WICHITA

Russell, Kansas

15-167-23227-0000 Shields


WELL LOG

02-12-2003



Operator: Grady Bolding Corporation
 Well: Lawson #1
 Commenced: January 23, 2003
 Completed: January 30, 2003
 Contractor: Shields Drilling Co.

Well Description: SW NW NW
 Sec. 36-13S-12W
 Russell Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	458'	Cmtd. w/250 sax

Elevation: 1,805' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Rock, sand, shale	135'	
Shale & sandstone	463'	
Shale & sand	660'	
Shale	697'	
Anhydrite	729'	
Shale	2,221'	
Shale & lime	2,707'	
Lime	3,042'	RTD