

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-195-20, 144 - 0000

LEASE NAME Huck

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4290 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR BHP Petroleum (Americas) Inc.

SEC. 36 TWP. 11S RGE. 21 (X) or (W)

ADDRESS 5555 NW Grand Blvd., Ste. 200 Okla. City 73112

COUNTY Trego

PHONE# (405) 943-8486 OPERATORS LICENSE NO. 5457

Date Well Completed 01/15/70

Character of Well Oil

Plugging Commenced 07/31/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 08/02/89

The plugging proposal was approved on 07/27/89 (date)

by Shari Feist Albrecht (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3875' Bottom 3886' T.D. 3889'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Heeb. 3528'	Water	Surface	216'	8-5/8"	01/70	AUG 1 1989 CONSERVATION DIVISION Wichita, Kansas
Lans. 3565'	Water	Surface	3880'	4-1/2"	01/70	
BKC. 3792'	Water					
Marm. 3860'	Water					
Arbuckle 3875'	Oil					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set 4 sx cmt plug in 4-1/2" csg at 2370' w/ bailer. Shot 4-1/2" csg at 900' where well had been squeezed in the past. Squeezed 75 sx 65/35 poz cmt down 4-1/2" csg, pumped 100 sx 65/35 poz cmt down 8-5/8" x 4-1/2" annulus. Cut off wellhead below GL and welded on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, Kansas 67524


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BHP Petroleum (Americas) Inc.
Paul Harryman c/o 5555 N.W. Grand Blvd., Suite 200

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Robert W. Eggert, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert W. Eggert Jr.

(Address) 5555 N.W. Grand Blvd., Suite 200
 Oklahoma City, Oklahoma 73112



SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 89

Virginia J. Frame
 Notary Public