

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name John Huck "A" Well No. 4

Location C W/2 NW NW Sec. 31 Twp. 11 Rge. (E) (W) 20

County Ellis Total Depth 3959'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:30 P Day 2 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3959' 8 5/8 csg set at 208' cwc 150 sk

5 1/2 csg set at 3938' cw 150 sk cem. DW tool at 1716' cem #650 sx. TC 718'

5 1/2 csg PBD 3919' & perf. (3869-3901)

Filled 5 1/2 csg W/sd (3850-3919) dumped 5 sk cem W/dump bailer. (3815-3850)

Set 5 1/2 wood plug at 810' -- poured 30' sd -- dumped 3 sk cem W/dump bailer. (755-810)

Cutoff and recovered 690' of 5 1/2 csg.

Set rock & sand bridge (208-200)

Filled with readymix cem from 200' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Prof. Messer  
Well Plugging Supervisor

INVOICED

DATE 11/5/73

INV. NO. 8118-10