

15-051 - 02368-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1963

12-10-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Co

Complete Address: Box 649 Mc Cook, Nebraska

Lease Name J.L. Caskey AUB Well No. 3

Location NW NE NE Sec. 31 Twp. 11 Rge. (E) (W) 20

County Ellis Total Depth 3872

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 2PM Day 7 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 310' circulated with cement - 5 1/2" 3862' with 150 sax cement -
squeezed with cement at 1049 & 938'

Filled with sand to 3850', set 4 sax cement with dump bailer - pulled
840' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550'
(20 sax Gel) displaced 20 sax cement through 5 1/2" at 550', heavy mud to
200' displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge
and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Petty
Well Plugging Supervisor

DATE 12/11/63

INV. NO. 8368-u