

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co.

Complete Address P. O. Box 1201 Wichita, Kansas

Lease Name John Huck "A" Well No. @ 5

Location SW SE NE NW Sec. 31 Twp. 11 Rge. (E) (W) 20

County Ellis Total Depth 3891'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 P Day 11 Month 6 Year 1974

The above well was plugged as follows:

RTD 3891' 8 5/8 csg set at 246' cwc Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 6/12/74
INV. NO. 9296-W