

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- -L

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Marilyn Chesney

Complete Address 201 W. 34th St, Hays, Ks. 67601

Lease Name ~~Caskey~~ J.L. Caskey Well No. S.W.D. System FWB KC

Location SW SW NE Sec. 31 Twp. 11 Rge. 20 (East) (West)

County Ellis Total Depth 3962'

Abandoned Oil Well Gas Well Input Well SWD Well XXXXX D&A

Other well as hereinafter indicated 5 1/2" pipe in to at 1048'

Plugging Contractor Halliburton Survices

Address 1100 E. 8th. St., Hays, Ks. 67601 License No.

Operation Completed: Hour: 11:30 AM Day: 12 Month: May Year: 1982

Plugging Operations attended by Agent?: All XXXXX Part None

The above well was plugged as follows:

8 5/8"-294' S.P. cut. w/175 sacks common. 5 1/2" set at 3867' w/150 sacks common
May 10-82 Rigged up pulling unit to clean out 1001' of 2 1/2" cement lined tubing
May 11-82 Drilled out iron-sulfied w/1" tubing to 1166' & circulated hole clean
May 12-82 Ordered 200 sacks 50/50 posmix 4% Gel.-3% Cal.Cl., Pumped into 8 5/8"
5 sacks cement w/500 pounds pressure. Pumped into 1" tubing and spotted 195 sacks
cement to surface.

Amount of Surface Casing: 294' of 8 5/8"

I hereby certify that the above plugging instructions given as herein stated.

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 12-6-82 signed:

Conservation Division Agent

INV. NO. 1753-W