

15-051-01324-0000

RECEIVED  
STATE CORPORATION COMMISSION

DEC 23 1959

CONSERVATION DIVISION  
Wichita, Kansas

*R*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: SE SW SE Sec. 27 Twp. 11 Rge. 16 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3310

I have this date completed supervision of plugging of:

Lease Name: Bowlby Well No. 1

Operator's Full Name: John O. Farmer

Complete Address: Russell, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 18 Month 12 Year 59

The above well was plugged as follows:

8 5/8" 965' circulated with cement - 5 1/2" 3300' with 125 sax cement.

PB to 3052' perforated v 3042'

Filled with sand to 3030', set 4 sax cement with dump bailer, pulled 2530'

5 1/2" to 350', circulated with heavy mud through 5 1/2" at 350' ( 27 sax Gel),

displaced 35 sax cement through 5 1/2" at 350', heavy mud to 35', set bridge

and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Jewel M. Ogden*  
Conservation Division Agent

Reviewed: *J. Lewis Burk*  
Field Supervisor

Remarks:

INVOICED  
DATE 1/14/60  
INV. NO. 556-w