

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
1-8-1963
JAN 8 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Solar Air Co

Complete Address: 1117 Union Natl Bldg - Wichita Kansas

Lease Name Schmitt Well No. 1

Location N 2 W Sw Sec. 1 Twp. 13 Rge. 16 (E) (W)

County Ellis Total Depth 3317

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Operation Completed: Hour 6 PM Day 1 Month Jan Year 1963

The Above well was plugged as follows:

T.D. 3317' - 8 5/8" - 1035' - 5 1/2" at 3312' - Perfo-3071-76

Sand to 3060' topped with 4 sac cement. Shot 5 1/2" at 2940'

and pulled same out of hole. Filled hole with chunks mud

to 450' and displaced 20 sac cement, mud to 18' and 20 sac cement

mud to 40' built rock bridge and 10 sac cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hubert P. Lucker
Well Plugging Supervisor

DATE 1/10/63

INV. NO. 6394-W