

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE NE NW

SEC. 1 TWP. 13 RGE. 16 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. D-1 Lease ~~Solar Oil Corp~~ Weiland

Operator Solar Oil Corp. Address 1117 W. 105th, Wichita, Kans

Field Fairport County Ellis

Total Depth 3492 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 975' circulated with cement - 5 1/2" at 3491, 100 sax

behind - Lane-Wells plugs 3453', perforations at 3062' -

Filled with chat to 3050', set 5 sax cement w th dump bailer,

pulled 2800' 5 1/2", mudded hole to 250', set wood plug, rock

and 15 sax cement, mudded to 35', set rock bridge and 10 sax

cement

**PLUGGING**  
FILE SEC LT 13 R 16 W  
BOOK PAGE 134 LINE 9

[Signature]  
District Conservation Agent

Date 1-13-50

JAN 16 1950  
1-18-1950