

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza Wichita, Kansas

Lease Name Perschisne Well No. 6

Location SW SW SE Sec. 1 Twp. 13 Rge. 16 (E) (W) X

County Ellis Total Depth 3343

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Csg., Inc.

Address: Great, Bend, Kansas. License No. 399

Operation Completed: Hour 5 P Day 17 Month 6 Year 1966

The Above well was plugged as follows:

Total Depth 3343 8 5/8 at 960 cwc. 5 1/2 at 3332 cw 75 sc

Filled with sand to 3320 and dumped 5 sc. cement with dump bailer.

Filled hole with mud to 500 Ft. Set bridge and 25 Ft. rock and 6 vds.

ready mix cement to base of celler.

RECEIVED

STATE CORPORATION COMMISSION

6-20-1966

JUN 20 1966

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo Murray
Well Plugging Supervisor

DATE 6/20/66

INV. NO. 3411-W

2912
3582
375
2957

75
375