

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-205- 19840-00-00
 NW NW NE Sec/Twp/Rge Sec 16 T29S R17E
5266 (GPS) feet from south section line
2019 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
 Lease/Well# Stich North - Wiles gps# MCD 17
 County Wilson
 Well Total Depth 850 (est) feet
 Production Pipe: NA Size Feet NA
 Surface Casing: NA Size Feet NA
 AB oil well XXXXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____
 Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097
 Address: 19450 Ford Road, Chanute, Kansas 66720
 Company to plug at: _____ Hour: _____ Day: 23 Month: 7 2009
 Plugging proposal received from: Sam Kepley
 Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730
 Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning
 TECHNICIAN
 Plugging attended by Agent: All _____ Part _____ None XXXXXX
 Operations Completed: Hour: _____ Day: 23 Month: 7 2009
 Actual Plugging Report: 7' of 10" surface pipe was set to bring well to surface. The well was washed down to 45' where the pipe hit cement. The drilling rig was moved to the location and the well was drilled to 25' thru iron. The drilling rig was moved off location. A rag packer on 2" pipe was cemented in at 15'. The following day, the well was then squeeze plugged thru the 2" rag packer and shut in at 500 psi. A total of 140 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

AUG 21 2009

Remarks: Control # 20090028-032
 (If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
 TECHNICIAN

KCC WICHITA