

To:
 STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-205- 19842- 00-00
 NE NW NE Sec/Twp/Rge Sec 16 T29S R17E
4730 (GPS) feet from south section line
1814 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
 Operator: State Of Kansas Fee Fund
 Name & Stich North Project
 Address _____
 AB oil well XXXXXX Gas Well _____

Lease/Well# Stich North-Wiles gps# MCD 19
 County Wilson
 Well Total Depth 850 (est) feet
 Production Pipe: 2 Size Feet NA
 Surface Casing: NA Size Feet NA
 SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 29 Month: 6 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part XXXXXX None _____

Operations Completed: Hour: _____ Day: 29 Month: 6 2009

Actual Plugging Report: 4' of 8" surface pipe was set to bring well to surface. A 1" pipe was

lowered to 400' to check for obstruction and for open hole. The 1" pipe was removed and the well perforated

at 600', 450', and 300'. A 1" cement string was then washed to 750' and the well pumped full of cement

from btm to top thru this cement string. A total of 39 sacks of portland cement were used to plug well.

The well was cut off below plow depth and the location restored.

RECEIVED
 KANSAS CORPORATION COMMISSION

Remarks: Control # 20090028-034

(If additional description is necessary, use BACK of this form.)

SEP 21 2009

I partially observed this plugging

Signed:

Alan M. Dunning
 TECHNICIAN

CONSERVATION DIVISION
 WICHITA, KS