

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19844-00-00
SW NW SW Sec/Twp/Rge Sec 16 T29S R17E
1498 (GPS) feet from south section line
4941 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Stich South Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Stich South-Winner gps# WIN 02
County Wilson
Well Total Depth 850 (est) feet
Production Pipe: 2 Size Feet NA
Surface Casing: NA Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 29 Month: 10 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part XXXXXX TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 29 Month: 10 2009

Actual Plugging Report: 1" pipe was lowered to 45' where cement was encountered. The drilling rig was moved to location and the well drilled to 220' inside the 2" production pipe. The well was then perforated at 200', 150', and 75'.

10-29-09: A 1" cement string was lowered to 220' and the well pumped full of cement from btm to top thru this cement string. A total of 40 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

DEC 02 2009

Remarks: Control # 20090027-002

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I partially observed this plugging

Signed:


TECHNICIAN