

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Stich South ProjectAddress AB oil well XXXXXX Gas Well Other well as hereinafter indicated: Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: Day: 3 Month: 11 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Clean well bore to TD and fill from btm to top with portland cement.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All Part XXXXXX None Operations Completed: Hour: Day: 3 Month: 11 2009

Actual Plugging Report: The well was perforated at 600', 300' and 150'. A 1" cement string was then lowered to 950' inside the 6". The well was pumped full of cement from btm to top thru this cement string. A total of 195 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090027-003

(If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed:


 TECHNICIAN

RECEIVED

DEC 02 2009

KCC WICHITA