

To:
 STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-205- 19853-00-00
 SE NW SW Sec/Twp/Rge Sec 16 T29S R17E
1650 (GPS) feet from south section line
4127 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
 Operator: State Of Kansas Fee Fund
 Name & Stich South Project
 Address _____
 AB oil well _____ Gas Well _____

Lease/Well# Stich South-Winner gps# WIN 14
 County Wilson
 Well Total Depth 850 (est) feet
 Production Pipe: 2 Size Feet NA
 Surface Casing: NA Size Feet NA
 SWD Well/ Input Well E-03946.9 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 6 Month: 11 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Clean well bore to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 6 Month: 11 2009

Actual Plugging Report: A string of 1" pipe was lowered to check for obstruction and open hole.

The 1" pipe was removed and the well perforated at 600', 300' and 150'. A 1" cement string was lowered to 775' inside the 2" production pipe and the well pumped full of cement. A total of 14 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

DEC 02 2009

KCC WICHITA

Remarks: Control # 20090027-022. The gps footages for this well are reasonably close to api#15-205-90241 in RBDMS
 (If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
 TECHNICIAN