

15-097-19003 (0000)

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 146-6 County: Kiowa

Location: NE NE NE Sec. 10 XX Twp. 27 Rge. 19 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4995

I have this date completed supervision of plugging of:

Lease Name: ~~Friends~~ Friends University ~~AUBKCC~~ Well No. 1

Operator's Full Name: Hilton Drilling Co.

Complete Address: Great Bend, Kans.

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kans. License No. \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 8 Month Dec Year 1958

The above well was plugged as follows:

308' of 8 5/8" surface casing circulated with cement. Top perf. 4805-  
4806'. Hole was filled with sand to 4800' and 5 sack cement dumped  
top sand with dump bailer. Pipe shot and pulled from 2700'. Hole  
filled with mud to 300'. A 10' rock bridge set from 300' to 290'  
20 sack cement placed top bridge. Heavy mud to 35'. A 10' rock bridge  
set from 35' to 25'. 10 sack cement placed from 25' to base of  
cellar.

Signed: *[Signature]*  
Conservation Division Agent

Reviewed: *[Signature]*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 10 T. 27 R. 19W  
BOOK PAGE 146 LINE 6

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1958  
CONSERVATION DIVISION  
Kansas