

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 - 22,868 - 0000 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Liberty Enterprises Inc.

Complete Address 308 W. Mill, Plainville, Ks. 67663

Lease Name Chrysler Well No. 3

Location SE SW SE Sec. 22 Twp. 11 Rge. 16 (East)(West)

County Ellis Total Depth 3380'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Pioneer Drilling Co. Inc.

Address 308 W. Mill, Plainville, Ks. 67663 License No.

Operation Completed: Hour: 6:45 AM Day: 12 Month: Feb. Year: 1982

Plugging Operations attended by Agent?: All Part None XXX

The above well was plugged as follows:

8 5/8"-226' S.P. cuc. W/ 140 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' W/ 70 sacks cement

2nd plug @ 220' W/ 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 226' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Weather advisory out for this area and only emergency traffic was allowed, due to snow blizzard.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 2-17-82

8443-W

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1982

CONSERVATION DIVISION
Wichita, Kansas