

15-051-03669-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 128-43

LOCATION NE NE SE

SEC. 21 TWP. 11 RGE. 16

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Baum 10 v v O. N. B. Co.

Operator Westgate Greenland Oil Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 5152' Feet.

(Describe briefly the manner in which the well was plugged)

9 5/8" casing at 1105' circulated with cement - 5 1/2" at 5107 with

70 sax cement behind - Filled with chat to 5100' set 5 sax cement

with dump bailer - pulled 2700', 5 1/2" - filled hole with heavy mud to

250', set wood plug, rock bridge and 15 sax cement - filled with

heavy mud to 30', set wood plug, rock and 10 sax cement.

**PLUGGING**  
FILE SEC. 21 T. 11 R. 16  
BOOK PAGE 107 LINE 43

[Signature]  
District Conservation Agent

Date 12-15-49 Div.

DEC 22 1949

STATE CORPORATION  
CONSERVATION  
DIVISION  
KANSAS