

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 96-7

LOCATION SW SW NW

SEC. 22 TWP. 11 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Glick

Operator Pabco Drg ~~Co~~ Inc, et al ^{AWB REC} Address 818 Cent Bldg Wichita,

Field _____ County Ellis

Total Depth 3137 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1015' circulated with 525 sax cement - 5 1/2" at 3137'

with 135 sax cement behind - Baker plugs to 3050' - top
perforations at 3038'.

Filled with sand to 3020', set 4 sax cement with dump bailer,

Pulled approx 1500' 5 1/2", filled with mud to 300', set rock

and 20 sax cement - mud to 35', set rock and 10 sax cement

to bottom cellar.

RECEIVED
 STATE CORPORATION COMMISSION

MAY - 5 1953

CONSERVATION DIVISION
 Wichita, Kansas

Edmund Perry
 District Conservation Agent

Date 4-30-53

PLUGGING
 FILE SEC 22 T 11 R 16W
 BOOK PAGE 96 LINE 7