

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22644-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name N-B Co., Inc.

Complete Address P. O. Box 506, Russell, Ks. 67665

Lease Name McGuire Well-No. #1

Location SE/SW/NW Sec. 21 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3360'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations

Address P. O. Box 506, Russell, Ks. 67665 License No. _____

Operation Completed: Hour: 5:30 PM. Day: 1st Month: Nov. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-247' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 9 1981

I hereby certify that the above plugging instructions were given as herein stated.

DATE 12-14-81

Signed: [Signature]
Conservation Division Agent

INV. NO. 8726-W