

15-051-20295-0000  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.  
Complete Address Shields Bldg., Russell, Kansas 67665  
Lease Name Chrisler Well No. 1  
Location NE NW SE Sec. 22 Twp. 11 Rge. (E) (W) 16  
County Ellis Total Depth 3372  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Forbes Casing Pulling Company  
Address Box 221 Great Bend, Kansas License No. 637  
Operation Completed: Hour 4:15 P Day 2 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 3372' 8 5/8 csg set at 260' cwc 200 sk.

5 1/2 csg set at 3255' cw 100 sk cmt.

5 1/2 csg PBTD 3226' with top perf. (3112')

Filled 5 1/2 csg W/sd (3100-3226) Dumped 5 sk cmt W/dump bailer. (3060-3100)

Cutoff and recovered 2432' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 25 sk gel W/5 sk hulls, plug and 120 sk

50-50 poz W/6% gel. Max. pres. 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 11/6/70

INV. NO. 2812-4