

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 60-9
LOCATION NW NW NE
~~RE SW SE~~

SEC. 9 TWP. 20 RGE. 11-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schuepfer

Operator West Supply Co Address Box 506 - Chase - Kans.

Field _____ County Barton

Total Depth 3328 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe - 8 1/2" - 245 ft. Circulated with cement.
5 1/2" at 3297 ft. - Cemented with 100 sacks of cement
Plugged back to 3290 ft. with chat - 5 sacks of
cement Dumped at 3290 ft. Shot off & pulled the
5 1/2" casing - Mud to 245 ft. Set Rock Bridge & 15 sacks
of cement at 245 ft. Mud to 30 ft. Plug &
10 sacks of cement at the surface -
West Supply Co. - Plugging Contract

PLUGGING
FILE NO. 9-110 NW
60-9

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1951
CONSERVATION DIVISION
Wichita, Kansas

C. M. Stough
District Conservation Agent

Date 2-9-51