

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 128-43
LOCATION 7E-7E-SW
SEC. 32 TWP. 17 RGE. 13W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Rowland

Operator Harwood Oil Company Address 1008 Bitting Bldg. Wichita K.

Field County Barton

Total Depth 3347 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 793' c.w.c. 5 1/2" casing set
3322.5 w/ 100 #1 Cem. Hole in casing at
3321' Sanded hole to 3315' dumped 5 #1
Cem. shot off and pulled 5 1/2" casing.
Filled with heavy mud to 300' set rock
bridge and dumped 20 #1 Cem. mud to 35'
rock bridge and 10 #1 Cem. to base
of cellar

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 - 1955
07-05-55
CONSERVATION DIVISION
Wichita, Kansas

Warren H. Harner
District Conservation Agent

Date July 1, 1955

PLUGGING
FILE SEC 22 | 17 | 13W
BOOK PAGE 148 LINE 43