

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 41-13

LOCATION NE-SW-SW

SEC. 13 TWP. 19 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Cerberhardt

Operator Pickrell Drilling Co., Inc. Address 705-4th N. Bldg. Wichita-Kans.

Field _____ County Barber

Total Depth 3335 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8 - 203 ft. Circulated with cement.
5/8 casing set at 3306 ft. cemented with 25 sacks cement
Plugged back to 3306 ft with chat. Dumped 5 sacks
of cement at 3300 ft. Shot off & pulled the 5/8 casing
Mud to 203 ft. Set Rock Bridge & 15 sacks of cement
at 203 ft. Mud to 30 ft. Plug & 10 sacks
of cement at the surface
Forbes Casing Pulling Co. - Plugged

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1950

CONSERVATION DIVISION
Wichita, Kansas

E. H. Stough
District Conservation Agent

Date 11-17-50

PLUGGING
FILE SEC. 13 TWP. 19 RGE. 11-W
BOOK PAGE 41 LINE 13