

15-051-20595-0000

Form CP-3  
Rev. 6-4-68

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Quinton Little

Complete Address Box 1509 Ardmore, Oklahoma 73401

Lease Name Murphy Well-No. 1

Location NE NE NW Sec. 26 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3444

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 3:20A Day 12 Month 3 Year 1970

The above well was plugged as follows:

RTD 3444' 8 5/8 csg set at 926' cwc 500 sk.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 20 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 10 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 3/19/70  
INV. NO. 1609-4