

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Lincoln

County. Sec. 8 Twp. 13S Rge. (E) 9 (W)

Location as "NE/CNWSW" or footage from lines. NW/NE/SE

Lease Owner Kewanee Oil Company

Lease Name Rahmeier Well No. 1

Office Address Box 360, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-25- 19 58

Application for plugging filed 11-25- 19 58

Application for plugging approved File 148-20 Verbal on 11-25- 19 58

Plugging commenced 11-25- 19 58

Plugging completed 11-25- 19 58

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes-Verbal on 11-25-58

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert J. Toman

Producing formation Depth to top Bottom Total Depth of Well 4030 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	509	8-5/8"	504	None
Kansas City	Dry	2912				
Mississippi	Dry	3392				
Hunton	Dry	3519				
Viola	Dry	3629				
Simpson	Dry	3682				
Arbuckle	Dry	3977	4030			
Total Depth		4030				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 4030' to 300'
Halliburton plug at 300'
1/4 sack wet hulls
20 sacks cement from 300' to 240'
Mud from 240' to 40'
Halliburton plug at 40'
1/4 sack wet hulls
10 sacks cement from 40' to cellar
2 sacks cement in rat hole
Finished plugging at 3:30 P.M.

STATE OF KANSAS
DEC 8 1958
CONSERVATION DIVISION
Wichita

Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Peter Blanda (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Peter Blanda

Box 360, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of December, 19 58

My commission expires September 21, 1961

Notary Public.

PLUGGING
FILE SEC 8 T.13 R9W
BOOK PAGE 148 LINE 20

KEWANEE OIL COMPANY

WELL RECORD: Rahmeier No. 1 Elevation: 1744' Cement Marker
(C.M. 4.00' above top of 8-5/8"
Casing Collar).

Located: 330' from the North line and 330' from the West line of
the SE/4, Section 8, T-13-S, R-9-W, Lincoln County, Kansas.

Contractors: Prime Drilling Company.

Drilling Commenced: November 7, 1958.

Drilling Completed: November 24, 1958.

Completion Date: November 25, 1958.

Total Depth: 4030' Cement Marker.

Initial Production: Plugged and abandoned.

Treating Record: None.

Perforating Record: None.

Sample Tops - C. M. Measurement

Heebner	2782	(-1038)
Toronto	2804	(-1060)
Douglas	2818	(-1074)
Douglas Sand	2836	(-1092)
Lansing-Kansas City	2910	(-1166)
Base Kansas City	3243	(-1499)
Mississippi	3396	(-1652)
Chatanooga	3500	(-1756)
Hunton	3540	(-1796)
Viola	3636	(-1892)
Simpson	3677	(-1933)
Arbuckle	3987	(-2243)
Total Depth	4030	(-2286)

Schlumberger Log Tops - C. M. Measurement

Heebner	2786	(-1042)
Toronto	2806	(-1062)
Douglas	2820	(-1076)
Douglas Sand	2839	(-1095)
Brown Line	2892	(-1148)
Lansing-Kansas City	2912	(-1168)
Base Kansas City	3229	(-1485)
Marmaton	3306	(-1562)
Mississippi	3392	(-1648)
Chatanooga	3481	(-1737)
Hunton	3519	(-1775)
Maquoketa	3550	(-1806)
Viola	3629	(-1885)
Simpson	3682	(-1938)
Arbuckle Congl.	3892	(-2148)
Arbuckle	3977	(-2233)
Total Depth	4030	(-2286)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1958
12-08-1958
CONSERVATION DIVISION
LINCOLN COUNTY, KANSAS

Casing Record

8-5/8" O.D. Casing (16 joints) set at 503.54' C.M. and cemented with
350 sacks pozmix with 1/4" floccle per sack and 2% calcium chloride.
Cement Circulated.

PLUGGING
FILE SEC 8 T13 R9w
BOOK PAGE 140 LINE 20

KEWANEE OIL COMPANY

WELL RECORD: Rahmeier Well No. 1 (Continued)

Formation Record

0	Surface
40	Lime & clay
140	Shale & lime
320	Shale & shells
360	Sand
570	Shale & shells
590	Sand & shale
1200	Shale
1240	Lime & shale
1508	Lime
1580	Lime & shale
1670	Lime
2420	Lime & shale
2525	Shale & lime
2850	Lime
2938	Lime & shale
3004	Lime & shale
3362	Lime
3420	Shale & sand streaks
3470	Lime & chert
3517	Lime & shale
3542	Shale
3585	Lime & chert
3622	Lime & shale
3637	Shale
3737	Lime
3792	Lime & shale
3862	Lime & sand
3885	Shale & lime
4030	Lime - Total Depth

Slope Tests

<u>Depth</u>	<u>Deviation</u>
100	1/4°
200	1/4°
350	3/4°
521	3/4°
1000	1/2°
1500	1°
2000	3/4°
2650	1°
3000	1/2°
3470	1/2°

Record by: Peter Blanda

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 - 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 13 R 9W
BOOK PAGE 148 LINE 20