

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mall or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Lincoln County. Sec. 21 Twp. 13 Rge. 9 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Sec SE SE

Lease Owner. Harry Miller

Lease Name. Vancura

Well No. 1

Office Address. c/o George Collins Petro. Bldg. Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. 9-5 19 48

Application for plugging filed. 9-7 19 48

Application for plugging approved. 9-7 19 48


Plugging commenced. 9-7 19 48

Plugging completed. 9-10 19 48

Reason for abandonment of well or producing formation. Dry

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well.

Producing formation. Depth to top. Bottom. Total Depth of Well. 1334 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	470'	470'
				10"	660'	660'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 400', set bridge at 375' and plugged with 30 sacks of cement. Filled hole with mud to within 10' of bottom of cellar, set bridge and filled with 10 sacks of cement.

09-23-1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Earl F. Wakefield  
Address. 307-B Union National Bank Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Earl F. Wakefield

(Address)

SUBSCRIBED AND SWORN to before me this 17 day of September 48

My commission expires 12-23-50

B. Jeanne Gaffney  
Notary Public.



15-105-00012-20-00

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg., Wichita, Kansas

Lease: Vancouver #1  
 Owner: Harry Miller  
 Contractor: Earl F. Wakefield  
 Comm: 8-15-48 Comp: 9-8-48

Location: Sec SE SE  
 Sec. 21 Twp. 13 N 9W  
 County: Lincoln, Kansas  
 Casing : 13-3/8" @ 470  
 10" @ 660

Soil	8	Salt	1180
Shell Rock	19	Shale	1225
Black Shale	23	Lime	1255
Lime	34	Blue Shale	1260
Grey shale	40	Grey Shale Shells	1265
Black shale	62	Hard Lime	1302
Shale Shells	60	Blue Shale	1355
Black Shale	120	Lime	1370
Lime Shells	125	Blue Shale	1390
Grey Shale	145	Red Rock	1385
Lime	150	Shale Shells	1435
Red Bed	160	Red Rock 1 BW	1455
Lime	165	Broken Lime	1525
Broken Lime	170	Red rock	1505
Red Bed	215	Lime	1670
Blue Shale	225	Blue Shale	1675
Brown Shale	235	Sandy shale water (1690-1700)	1690
Red Bed	285	Red Rock	1700
Red Rock	305	Sandy Lime	1735
Brown Shale	350	Red Rock	1745
Grey Sandy Shale 1/2 BW	352	Hard Lime	1775
Brown Shale	390	Red Rock	1780
Red Rock	400	Shale	1790
Lime 6 BW (415-20)	415	Hard Lime	1800
Shale	432	Red Rock	1805
Sand Rock full water(452-49)	455	Lime	1830
Sand	464	Red Rock	1834
Shale caving badly	470	Total Depth	1834
Blue Shale	490		
Grey Shale shells	510		
Blue shale 2 BW (552)	525		
Red Rock water	565		
Hard	580		
Sandy Lime	600		
Red Rock	645		
Hard Lime	652		
Shale	660		
Lime	675		
Red Rock	695		
Blue Shale	725		
Broken Red Rock & Shale	760		
Blue Shale	800		
Red Rock	812		
Blue Shale	830		
Red Rock	840		
Shale	885		
Blue Shale	990		
Salt	1010		
Shale	1030		

09-23-1948

STATE OF KANSAS } SE  
 COUNTY OF LINCOLN }

I hereby certify that the above is a true and correct copy of the log of the Vancouver #1 well located in SE SE SE of Section 21-13-9W Lincoln County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 17th day of September, 1948.

PLUGGING  
 FILE SET 21 (13-9W) Jeanne Daffney  
 BOOK PAGE 2 LINE 18

My Comm. Expires: 12-31-50