

15-119-20031-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Meade County. Sec. 13 Twp. 33S Rge. (E) 30 (W)

Location as "NE/CNW%SW%" or footage from lines C NE SE

Lease Owner Tilco, et al

Lease Name Evans Well No. 1

Office Address 200 Sutton Place Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-15 19 69

Application for plugging filed 7-15 19 69

Application for plugging approved 7-15 19 69

Plugging commenced 7-15 19 69

Plugging completed 7-15 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 6294 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				1472'	8 5/8"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 30 sacks cement @ 1472'
Plugged with 10 sacks cement @ 40'
2 sacks in rat hole and 2 sacks in mouse hole

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Subscribed and sworn to before me this 22nd day of July, 19 69

(Address) Ulanda Nichols
Ulanda Nichols Notary Public.

My commission expires April 1, 1971



DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	EVANS #1
LOCATION	C NE SE SECTION 13-33S-30W MEADE COUNTY, KANSAS
COMMENCED	6-23-69
COMPLETED	7-15-69

0	100	Surface Soil
100	500	Sand
500	870	Red Bed
870	1020	Red Bed, Gyp
1020	1203	Sand
1203	1465	Red Bed, Gyp
1465	1472	Anhydrite
1472	1500	Red Bed, Anhydrite
1500	2077	Red Bed Shells & Shale
2077	2605	Shale
2605	4619	Lime, Shale
4619	4782	Lime, Shale, Chert
4782	4970	Lime Shale
4970	5730	Lime
5730	5825	Lime, Sand
5825	5956	Shale, Lime
5956	6294	Lime
	<u>6294</u>	<u>RTD - D & A</u>

8 5/8" 24# new surface casing set @ 1472' cemented with 550 sacks 50/50
Posmix with 6% gel and 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Evans #1 well, located C NE SE of Section 13, Township 33 South, Range 30 West, Meade County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite


STATE OF KANSAS)
) SS
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1969
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of July, 1969.

Ulanda Nichols

Ulanda Nichols



My Commission Expires: