


WELL PLUGGING RECORD

15-119-00005-00+00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Meade County. Sec. 13 Twp. 33 Rge. 30 (W)  
Location as "NE/CNW/SW" or footage from lines 1980 fr S, 1980 fr West  
Lease Owner The Shamrock Oil and Gas Corporation  
Lease Name Stephen J. North et ux Well No. 1  
Office Address Box 631 - Amarillo, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 2, 19 55  
Application for plugging filed September 2, 19 55  
Application for plugging approved September 2, 19 55  
Plugging commenced September 2, 19 55  
Plugging completed September 2, 19 55  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation None Depth to top - Bottom - Total Depth of Well 5,845 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand and red beds	Water	0	600	13-3/8	638	-0-
Red bed, shale	-	-	-	9-5/8	2731	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back hole from 5845' to 500' with heavy mud. Pushed 9-5/8" Halliburton plug down casing to 500'. Spotted 35 sacks cement on top of plug from 500' to 424'. Spotted heavy mud from 424' to 35'. Pushed 9-5/8" Halliburton plug down casing to 35'. Spotted 15 sacks cement from 35' to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company  
Address Great Bend, Kansas

STATE OF Texas, COUNTY OF Potter, ss.

Dan P. Long (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan P. Long

Box 631, Amarillo, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 55

My commission expires June 1, 1957

DORRIS RICHARDSON  
NOTARY PUBLIC  
Notary Public.  
RECEIVED  
STATE CORPORATION COMMISSION  
9-7-55  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 13 T 33 R 30W  
BOOK PAGE 142 LINE 6

Log Of

THE SHAMROCK OIL AND GAS CORPORATION

Stephen L. North et ux No. 1

Section 13, T33S, R30W, Meade County, Kansas

0 - 565	Sand, gravel
565 - 907	Red bed
907 - 1995	Red bed, gyp
1995 - 2237	Red bed, gyp, sand
2237 - 2368	Red bed, gyp, shale
2368 - 2429	Red bed, gyp, shale, anhydrite
2429 - 2582	Anhydrite, shale
2582 - 2852	Anhydrite
2852 - 3085	Dolomite
3085 - 3142	Lime
3142 - 4611	Lime, shale
4611 - 5003	Lime
5003 - 5845	Lime, shale

**PLUGGING**  
 FILE SEC 13 T33 R30W  
 BOOK PAGE 47 LINE 6