

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 24 TWP. 28S RGE. 18W E/W
 Location as in quarters or footage from lines:
C - S-E - S-W

Lease Owner Voyager Petroleum
 Lease Name Keller Well No. B-1
 Office Address 110 16th St./Suite 800/Denver, CO 80202
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas Oil
 Date Well Completed 8/21/1977
 Application for plugging filed 10/25/1982
 Plugging commenced 1/15/1983
 Plugging completed 2/7/1983
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Durant / Tarbutton

Producing formation _____ Depth to top _____ bottom _____ T.D. 4886'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	350	none
				4 1/2	4886	2442

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Plugged back at 4850. Sand from 4850
to 4790. Dumped 4 sacks of cement with dump bailer from 4790 to 4760.
Ripped at 3000 - 2900. Pipe moving, then stopped. Had to rip at 2600 and 2424 before
pipe came free. Dowell pumping. Top plug. 4 sacks of hulls. 15 sacks of jell.
50 sacks of cement. 15 sacks of jell. 1 sack of hulls. Plug. 100 sacks of cement.
4% jell. 3% c.c. I talked to Bob Tarbutton for top 50 - 50 - Poz. Randy on location.
Plugged 2/4/1983 at 10:00 a.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barker, ss.
Arnold R. Morgenstern (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Arnold R. Morgenstern
Medicine Lodge, Mo.
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1983

RECEIVED
J. Durant / Tarbutton
 Notary Public.

My Commission expires: April 4, 1986.

FEB 14 1983

CONSERVATION DIVISION
 WICHITA, KANSAS