

15-081-39028-00-00
28-30-33W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL
Farm- Rooney No. 1

SEC. 28 T. 30 R33W
C NW SE

Total Depth. 5722'
Comm. 2-15-63 Comp. 3-15-63
Shot or Treated.
Contractor. Lohmann-Johnson
Issued. 12-28-63

County Haskell
KANSAS



Elevation. 2945' DF

Production. 1,635,000 CFG + 10½
GO + 1½ GWP

Figures Indicate Bottom of Formations.

redbed	220
sand & redbed	1548
shale, redbed & Anhydrite	1810
redbed	1888
redbed, sand & shale	2372
shale	2875
Anhydrite & shale	3015
lime & sand	3340
lime	3542
chalk & lime	3655
lime & shale & chalk	3815
shale & lime	4072
lime	4243
lime & shale	4485
lime	4674
lime & shale	4817
lime	5019
lime & shale	5252
shale & lime	5357
sand, shale & lime	5386
sand & lime	5397
lime & shale	5433
lime	5722
Total Depth	

TOPS: LOG	
Winfield	2702
Heebner	4088
Toronto	4112
Lansing	4178
"D"	4628
Marmaton	4787
Morrow	5244
Sand	5336
Chester	5362
St. Geneva	5434
St. Louis	5518