

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

7/29/10

Operator: License # 32825
Name: Pioneer Exploration, LLC
Address: 15603 Kuykendahl Suite 200
City/State/Zip: Houston, Texas 77090
Purchaser: NCRA
Operator Contact Person: Erick A. Rodriguez
Phone: (281) 893-9400 x. 210
Contractor: Name: Warren Drilling LLC
License: 33724
Wellsite Geologist: Patrick J. Deenihan

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 31 2008

CONSERVATION DIVISION
WICHITA, KS

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core WSW, Expl., Cathodic, etc)

CONFIDENTIAL
JUL 29 2008

If Workover/Re-entry: Old Well Info as follows:
Operator: KCC

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

04/07/08 04/16/08 05/15/08
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 055-21972-00-00
County: Finney
 - NE - NE - NW Sec. 19 Twp. 22 S. R. 33 East West
330 feet from S / (N) (circle one) Line of Section
2970 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Garden City "B" Well #: 2-19
Field Name: Damme
Producing Formation: Mississippi
Elevation: Ground: 2904 Kelly Bushing: 2917
Total Depth: 4951 Plug Back Total Depth: 4902
Amount of Surface Pipe Set and Cemented at 337 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 2691 Feet
If Alternate II completion, cement circulated from 4951
feet depth to surface w/ 1200 sx cmt.

Drilling Fluid Management Plan AH II NH 10-27-08
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature: Erick Rodriguez
Title: Operations Coordinator Date: 07/29/08

Subscribed and sworn to before me this 29th day of July, 2008.

Notary Public: Clark Ordas

Date Commission Expires: DEC. 13, 2010

KCC Office Use ONLY
 Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

 **Clark Ordas**
Notary Public, State of Texas
My Commission Expires:
December 13, 2010

Operator Name: Pioneer Exploration, LLC Lease Name: Garden City "B" Well #: 2-19
 Sec. 19 Twp. 22 S. R. 33 East West County: Finney

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: CNL/CDL MEL, DIL, CBL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See attached
--	--

RECEIVED
 KANSAS CORPORATION COMMISSION
JUL 31 2008
 CONSERVATION DIVISION
 WICHITA, KS

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24	337	Common	225	3% cc w/ 2% gel
Production	7-7/8"	4-1/2"	10.5	4950	C/C-lite/ASC	1200	10% salt, 2% gel, 5# gilsonite; 1/4# flo-seal

CONFIDENTIAL
 JUL 29 2008

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone		RCC		

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4734 - 4739		

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
		2-3/8"	4765				
Date of First, Resumerd Production, SWD or Enhr. 05/18/08			Producing Method				
			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbbs.	Gas Mcf	Water Bbbs.	Gas-Oil Ratio	Gravity		
4	0	10	0	27.6			

Disposition of Gas METHOD OF COMPLETION Production Interval

Vented Sold Used on Lease
 Open Hole Perf. Dually Comp. Commingled
(If vented, Submit ACO-18.)
 Other (Specify) _____

Garden City "B" #2-19
Damme Field
Finney County
API No. 15-055-21972-00-00

Tops and base of formations penetrated

Name	Top	Datum
Herington	2514	+403
Krider	2552	+365
Winfield	2599	+318
Heebner Shale	3812	-895
Lansing	3860	-943
Kansas City "B"	4344	-1427
Pawnee	4442	-1525
Cherokee Shale	4486	-1569
Morrow Shale	4678	-1761
Morrow Sand	4733	-1816
Mississippi/St. Louis	4782	-1865

CONFIDENTIAL
JUL 29 2008
KCC

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 31 2008

CONSERVATION DIVISION
WICHITA, KS

233798


SCANNED
4-11-08

ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

PRIORITY INVOICE

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906
Voice: (785) 483-3887
Fax: (785) 483-5566



Invoice Number: 113404
Invoice Date: Apr 9, 2008
Page: 1

Bill To:
Pioneer Exploration, LTD
P O Box 38
Spivey, KS 67142-0038

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
PioExp	Garden City #2-19	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Oakley	Apr 9, 2008	5/9/08

Quantity	Item	Description	Unit Price	Amount
225.00	MAT	Class A Common	14.20	3,195.00
4.00	MAT	Gel	18.75	75.00
8.00	MAT	Chloride	52.45	419.60
237.00	SER	Handling	2.15	509.55
75.00	SER	Mileage 237 sx @.09 per sk per mi	21.33	1,599.75
1.00	SER	Surface	917.00	917.00
37.00	SER	Extra Footage	0.80	29.60
75.00	SER	Mileage Pump Truck	7.00	525.00
1.00	EQP	Wooden Surface Plug	68.00	68.00

CONFIDENTIAL
JUL 29 2008
KCC

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 31 2008
CONSERVATION DIVISION
WICHITA, KS

DESCRIPTION Cementing
ACCOUNT # 1600-15
WELL NAME GARDEN CITY #2-19
APE# 0804 D013 K KS154102
DATE 4-11-08 APPROVED _____

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 733.85

ONLY IF PAID ON OR BEFORE

May 9, 2008

Subtotal	7,338.50
Sales Tax	232.97
Total Invoice Amount	7,571.47
Payment/Credit Applied	
TOTAL	7,571.47

ALLIED CEMENTING CO., INC. 32243

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE <u>4-7-08</u>	SEC <u>19</u>	TWP. <u>22</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>4:45 p.m.</u>	JOB START <u>4:30 a.m.</u>	JOB FINISH <u>5:00 a.m.</u>
<u>Garden City</u> LEASE	WELL # <u>2-19</u>		LOCATION <u>Holcomb</u> <u>8 N 1/2 E Sinto</u>	COUNTY <u>Finney</u>		STATE <u>Ks</u>	
OLD OR <u>(NEW)</u> (Circle one)							

CONTRACTOR Warren Drilling Rig #18 OWNER same

TYPE OF JOB	<u>Surface</u>
HOLE SIZE	<u>12 1/4"</u>
CASING SIZE	<u>8 5/8"</u>
TUBING SIZE	
DRILL PIPE	
TOOL	
PRES. MAX	
MEAS. LINE	
CEMENT LEFT IN CSG.	<u>15'</u>
PERFS.	
DISPLACEMENT	<u>20.5 DBE</u>

CEMENT	
AMOUNT ORDERED	<u>225 sks com</u>
	<u>3% cc 2% gel</u>
COMMON	<u>225 sks @ 14.20 3195.00</u>
POZMIX	@
GEL	<u>4 sks @ 18.25 75.00</u>
CHLORIDE	<u>8 sks @ 52.45 419.60</u>
ASC	@

EQUIPMENT	<u>JUL 29 2008</u>
PUMP TRUCK	CEMENTER <u>Andrew KGC</u>
# <u>423-281</u>	HELPER <u>Alan</u>
BULK TRUCK	
# <u>218</u>	DRIVER <u>Wil</u>
BULK TRUCK	
#	DRIVER

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 31 2008

HANDLING	<u>237 sks @ 2.15 509.55</u>
MILEAGE	<u>99 sk/mile 1599.75</u>
TOTAL	<u>5798.90</u>

REMARKS:

CONSERVATION DIVISION
WICHITA, KS

SERVICE

<u>Cement did circulate</u>	DEPTH OF JOB	<u>337'</u>	
	PUMP TRUCK CHARGE		<u>912.00</u>
	EXTRA FOOTAGE	<u>37' @ .80</u>	<u>29.60</u>

(A) Nothing in this contract shall be construed as a warranty by ALLIED of the success or the effectiveness of the result of any work done or merchandise used, sold, or furnished under this contract.

(B) Nothing in this contract shall be construed as a warranty of the accuracy or correctness of any facts, information, or data furnished by ALLIED or any interpretation of tests, meter readings, chart information, analysis of research, or recommendations made by ALLIED, unless the inaccuracy or incorrectness is caused by the willful misconduct or gross negligence of ALLIED or its employees in the preparation or furnishing of such facts, information or data.

(C) Work done by ALLIED shall be under the direct supervision and control of the CUSTOMER or his agent and ALLIED will accomplish the job as an independent contractor and not as an employee or agent of the CUSTOMER.

2. More specifically:
 by defective materials, products or supplies.
 provided, and ALLIED shall not be liable for any consequential, special, incidental, or punitive damages resulting from or caused remedy with regard to any defective merchandise shall be the repair or replacement thereof or allowance for credit as herein RANTY AS TO MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE, CUSTOMER'S sole and only RANTY IS APPLICABLE, EITHER EXPRESS OR OTHERWISE IMPLIED, IN FACT OR IN LAW, INCLUDING ANY WAR-

235057

ALLIED CEMENTING CO., LLC

Cementing & Acidizing Services

SCANNED
4-24-08

PRIORITY INVOICE

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906
Voice: (785) 483-3887
Fax: (785) 483-5566

RECEIVED
APR 24

Invoice Number: 113557
Invoice Date: Apr 18, 2008
Page: 1

Bill to:
Pioneer Exploration, LTD
P O Box 38
Spivey, KS 67142-0038

Customer ID	Well Name / or Customer P.O.	Payment Terms
PioExp	Garden City B#2-19	Net 30 Days
Job Location	Camp Location	Service Date
KS	Russell	Apr 18, 2008
		Due Date
		5/18/08

Quantity	Item	Description	Unit Price	Amount
150.00	MAT	Class C Premium Plus	17.35	2,602.50
650.00	MAT	Lightweight Class A	12.65	8,222.50
3,250.00	MAT	Gilsonite	0.80	2,600.00
163.00	MAT	Flo Seal	2.25	366.75
915.00	SER	Handling	2.15	1,967.25
50.00	SER	Mileage 915 sx @.09 per sk per mi	82.35	4,117.50
1.00	SER	Production String - Top String	1,075.00	1,075.00

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 31 2008
CONSERVATION DIVISION
WICHITA, KS

DESCRIPTION Cementing
ACCOUNT # 1630-15
WELL NAME Garden City B#2-19 KS. 15902
AFE# 780415013
DATE 4-24-08 APPROVED _____

ALL PRICES ARE NET, PAYABLE 30 DAYS FOLLOWING DATE OF INVOICE. 1 1/2% CHARGED THEREAFTER. IF ACCOUNT IS CURRENT, TAKE DISCOUNT OF

\$ 2095.15

ONLY IF PAID ON OR BEFORE

May 18, 2008

Subtotal	20,951.50
Sales Tax	855.09
Total Invoice Amount	21,806.59
Payment/Credit Applied	
TOTAL	21,806.59

ALLIED CEMENTING CO., LLC. 31854

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>4-17-08</u>	SEC. <u>19</u>	TWP. <u>22S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>5:00 AM</u>	JOB START <u>4:15 PM</u>	JOB FINISH <u>5:45 PM</u>
LEASE <u>GARDEN CITY #8</u>	WELL # <u>2-19</u>	LOCATION <u>GARDEN CITY 10N-5 1/2 W- 5 SW</u>			COUNTY <u>FINNEY</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>WARREN DRILL RIG #19</u>	OWNER <u>SAME</u>
TYPE OF JOB <u>Production STRING TOP STAGE</u>	
HOLE SIZE <u>7 7/8"</u>	T.D. <u>4950'</u>
CASING SIZE <u>4 1/2"</u>	DEPTH <u>4266'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>D-V</u>	DEPTH <u>2693</u>
PRES. MAX	MINIMUM
MEAS. LINE <u>CONFIDENTIAL</u>	SHOE JOINT <u>21.31'</u>
CEMENT DEPT IN CSG. <u>21.31'</u>	
PERFS. <u>JUL 29 2008</u>	
DISPLACEMENT <u>42 3/4 BBLs</u>	

KCC EQUIPMENT

PUMP TRUCK # <u>H22</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE</u>
BULK TRUCK # <u>218</u>	DRIVER <u>REX</u>
BULK TRUCK # <u>394</u>	DRIVER <u>LARENSE</u>
# <u>377</u>	<u>KELLY</u>

CEMENT	AMOUNT ORDERED	<u>150 SKS CLASS "C"</u>
		<u>650 SKS LITE 5" GILSONITE 1/4" FLO-SEAL</u>
<u>CLASS "C"</u>		
650 SKS	<u>150 SKS</u>	@ <u>17.35</u> <u>2602.50</u>
POZMIX	@	
GEL	@	
CHLORIDE	@	
ASC	@	
<u>LITE 650 SKS</u>	@ <u>12.65</u>	<u>8222.50</u>
<u>GILSONITE 3250 #</u>	@ <u>.80</u>	<u>2600.00</u>
<u>FLO-SEAL 163 #</u>	@ <u>2.25</u>	<u>366.75</u>
HANDLING <u>915 SKS</u>	@ <u>2.15</u>	<u>1967.25</u>
MILEAGE <u>98 PER SKT</u>	MILE	<u>4117.50</u>
TOTAL		<u>19876.50</u>

REMARKS:
625 MIX 650 SKS LITE 5" GILSONITE
1/4" FLO-SEAL 150 SKS CLASS "C"
WASH TRUCK + LINE, DISPLACE
42 3/4 BBLs WATER
PLUG RAT HOLE WITH 15 SKS MOUSE HOLE 10SKS
CEMENT dtd CRL
PLUG LANDED AT 2500 PSI.
Tool Held.

THANK YOU

SERVICE

DEPTH OF JOB	<u>2693'</u>
PUMP TRUCK CHARGE	<u>1075.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>50 MP</u>	@ <u>NC</u>
MANIFOLD	@
	@
	@

TOTAL 1075.00

CHARGE TO: PIONEER EXPLORATION
 STREET _____
 CITY _____ STATE _____ ZIP _____

RECEIVED PLUG & FLOAT EQUIPMENT
KANSAS CORPORATION COMMISSION

JUL 31 2008 @ _____
 @ _____
 CONSERVATION DIVISION @ _____
 WICHITA, KS @ _____
 @ _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment
 and furnish cementer and helper(s) to assist owner or

235056

ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906
Voice: (785) 483-3887
Fax: (785) 483-5566

SCANNED 4-24-08
REPRINTED
APR 24

PRIORITY INVOICE

Invoice Number: 113556
Invoice Date: Apr 18, 2008
Page: 1

Bill To:
Pioneer Exploration, LTD
P O Box 38
Spivey, KS 67142-0038

Customer ID	Well Name# or Customer P.O.	Payment Terms	
PioExp	Garden City 'B'#2-19	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Russell	Apr 18, 2008	5/18/08

Quantity	Item	Description	Unit Price	Amount
4.00	MAT	Gel	18.75	75.00
200.00	MAT	ASC Class A	16.75	3,350.00
200.00	MAT	Lightweight Class A	12.65	2,530.00
19.00	MAT	Salt	21.60	410.40
1,000.00	MAT	Gilsonite	0.80	800.00
50.00	MAT	Flo Seal	2.25	112.50
460.00	SER	Handling	2.15	989.00
50.00	SER	Mileage 460 sx @ .09 per sk per mi	41.40	2,070.00
1.00	SER	Production String - Bottom Stage	1,812.00	1,812.00
50.00	SER	Mileage Pump Truck	7.00	350.00
1.00	EQP	AFU Float Shoe	434.00	434.00
1.00	EQP	Latch Down Plug Assembly	405.00	405.00
10.00	EQP	Centralizers	51.00	510.00
3.00	EQP	Baskets	169.00	507.00
1.00	EQP	Stage Collar	4,219.00	4,219.00

CONFIDENTIAL
JUL 20 2008

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 31 2008

CONSERVATION DIVISION
WICHITA, KS

DESCRIPTION Cementing

ACCOUNT # 1602-15
WELL NAME Garden City B#2-19 KS 15902
AFE# 0804100131
DATE 4-24-08 APPROVED _____

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF



ONLY IF PAID ON OR BEFORE

May 18, 2008

Subtotal	18,573.90
Sales Tax	827.88
Total Invoice Amount	19,401.78
Payment/Credit Applied	
TOTAL	19,401.78

ALLIED CEMENTING CO., LLC. 31853

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

ORLEY

DATE <u>4-17-08</u>	SEC. <u>19</u>	TWP. <u>225</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>5:00 AM</u>	JOB START <u>12:45 PM</u>	JOB FINISH <u>1:45 PM</u>
LEASE <u>GARDEN CITY '8</u>		WELL # <u>2-19</u>		LOCATION <u>GARDEN CITY 10N-5 1/2 W-S 2W</u>		COUNTY <u>FINNEY</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>Warren Orly Rig 18</u>	OWNER <u>SAME</u>
TYPE OF JOB <u>Production Stage # Bottom Stage</u>	
HOLE SIZE <u>7 7/8" T.D. 4950'</u>	CEMENT
CASING SIZE <u>4 1/2" DEPTH 4966'</u>	AMOUNT ORDERED
TUBING SIZE	<u>200 SKS ASC 10% SALT 5# GELSONITE 2% GEL</u>
DRILL PIPE	<u>200 SKS LITE 1/4" FLO-SEAL</u>
TOOL <u>D-U DEPTH 2693'</u>	
PRES. MAX	COMMON @
MEAS. LINE <u>CONFIDENTIAL</u>	POZMIX @
CEMENT LEFT IN CSG <u>JUL 29 2008 21.31'</u>	GEL <u>4 SKS @ 19.75 75.00</u>
PERFS.	CHLORIDE @
DISPLACEMENT <u>36 BBLs WATER 42 3/4 BBLs MUD</u>	ASC <u>200 SKS @ 16.25 3250.00</u>
EQUIPMENT <u>TOTAL 78 3/4 BBLs</u>	LITE <u>200 SKS @ 12.65 2530.00</u>

PUMP TRUCK CEMENTER <u>Terry</u>
<u>422</u> HELPER <u>Wayne</u>
BULK TRUCK
<u>373-308</u> DRIVER <u>Darrin</u>
BULK TRUCK
<u>377</u> DRIVER <u>Kelly</u>
<u>218 REX</u>
<u>394 LARENCE</u>

<u>SALT 19 SKS @ 21.50 410.00</u>
<u>GELSONITE 1000# @ 0.80 800.00</u>
<u>FLO-SEAL 50# @ 2.25 112.50</u>
HANDLING <u>460 SKS @ 2.15 989.00</u>
MILEAGE <u>94 PER SK/MILE 2070.00</u>
TOTAL 10336.40

REMARKS:

MIX 200 SKS LITE 1/4" FLO-SEAL
200 SKS ASC 10% SALT 5# GELSONITE
2% GEL. WASH TRUCK + LINES
DISPLACE 36 BBLs WATER 42 3/4
BBLs MUD TOTAL 78 3/4 BBLs.
PLUG LANDED AT 1600PST, FLOAT
HELD. DROP OPENING TOOL WAIT
15 MEN OPEN D-U TOOL CIRC 2 RUN
THANK YOU

SERVICE

DEPTH OF JOB <u>4966'</u>
PUMP TRUCK CHARGE <u>1812.00</u>
EXTRA FOOTAGE @
MILEAGE <u>50 MI @ 7.00 350.00</u>
MANIFOLD @
@
@

TOTAL 2162.00

CHARGE TO: PIONEER Exploration

STREET _____

CITY _____ STATE _____

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 31 2008

CONSERVATION DIVISION
WICHITA, KS

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or

<u>4 1/2" PLUG & FLOAT EQUIPMENT</u>	
<u>1- AFU Float Shoe</u>	<u>434.00</u>
<u>1- Latch down Plug Assy</u>	<u>405.00</u>
<u>10- CENTRALIZER @ 57.00</u>	<u>570.00</u>
<u>3- BASKETS @ 169.00</u>	<u>507.00</u>
<u>1- STAGL COLLAR @</u>	<u>4219.00</u>