

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-081-10005-0000 0001

LEASE NAME DUDLEY TOWNSHIP

TYPE OR PRINT

NOTICE: Fill out completely  
and return to GORS. Div.  
office within 30 days

WELL NUMBER SWD 2

660' FSL Ft. from S Section Line

1980' FEL Ft. from E Section Line

SEC. 12 TWP. 30S RGE. 34W ☒ or ☐ (W)

COUNTY HASKELL

Date Well Completed 1963

Plugging Commenced 5/3/00

Plugging Completed 5/5/00

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1357 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well SWD

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/4/00 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation TOPEKA Depth to Top 2975' GL \_\_\_\_\_ Bottom 3840' T.D. 4584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
TOPEKA	WTR	3736'	3753'	8 5/8"	765'	0
				5-1/2"	4848'	779.02'
						CONSERVATION DIVISION Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

5/3/00 P&A Operations witnessed by Steve Durant, KCC. MIRU Pump 85 BBL 9 PPG 36 CP mud. Circ hole Spot 10 sx cmt plug on CIBP. Cut csg @ 774'. Pump 55 BBL 9 PPG 36 CP mud. Circ hole Spot 50 sx cmt plug @ 741'. Disp csg w/14 BBL mud. Spot 30 sx cmt plug @ 345'. Disp csg w/ 6 BBL mud. Spot 10 sx cmt plug @ 40'. Circ cmt to sfc. Cut 8-5/8" csg 4' BGL. Top off stub w/ cmt weld on trash cvr-ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

ANGIE HERNANDEZ (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Angie Hernandez

(Address) 5205 N. O'CONNOR BLVD. RM 1357 IRVING TX 75039



DEBORAH POLLOCK  
Notary Public, State of Texas  
My commission expires 04-02-2001

SUBSCRIBED AND SWORN TO before me this 19TH day of JUNE, 20 00

My Commission Expires: 4-2-2001

Notary Public

USE ONLY ONE SIDE OF EACH FORM

Form CP-4  
Revised 05-88