


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County. Sec. 21 Twp. 11S Rge. 16W ~~ME~~ KWX
Location as "NE/CNWKSWK" or footage from lines NW SE SW
Lease Owner Century Oil Company
Lease Name Potter Well No. 2
Office Address 925 O.W. Garvey Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 13, 1972
Application for plugging filed Verbal Application 19 72
Application for plugging approved Verbal Approval 19 72
Plugging commenced January 13, 1972
Plugging completed January 13, 1972
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	968'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,370 feet (rotary total depth) to 400 feet. Set plug at 400 feet and cemented with 25 sacks cement.
Filled hole with heavy rotary mud from 400 feet to 40 feet. Set solid plug at 40 feet and cemented with 10 sacks cement to cellar, 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. Dean Britting, Agent (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Dean Britting
200 North Main, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 24th day of January, 19 72

Elsie Willison
Elsie Willison Notary Public.

KANSAS GEOLOGICAL SOCIETY 15-05120794-0000
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Century Oil Company

SEC. 21 T. 11S R. 16W
LOC. NW SE SW

FARM Potter

NO. 2

COUNTY Ellis

KANSAS

TOTAL DEPTH 3,370'

COMM. January 5, 1972

COMP. January 13, 1972

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

CASING

20 10

15 8-5/8" 968'

12 6

13 5

cemented w/225 sxs cement ELEVATION 3,370' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	25'
Post Rock	100'
Shale	280'
Shale and Redbed	796'
Shale	958'
Anhydrite	1,003'
Sand and Shale	1,115'
Shale	1,590'
Shale & Lime Stringers	1,645'
Shale and Shells	1,775'
Shale and Lime	1,896'
Lime and Shale	2,900'
Lime	3,075'
Lime and Shale	3,120'
Lime	3,239'
Lime and Shale	3,360'
Lime	3,370'
Rotary Total Depth	3,370'

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1972
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing
to be a true and correct log of the above
described well as shown by the drilling
reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary
Public in and for said county and state
this 24th. day of January, 1972.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1974